

May 18, 2023

REQUEST FOR QUOTATIONS

The Philippine Council for Health Research and Development (PCHRD), through its Bids and Awards Committee (BAC), requests PhilGEPS registered suppliers to submit **sealed quotations for the one (1) lot Labor, Supplies, and Materials for the Rehabilitation of Electrical System for the Office Space at Titanium Building with a total approved budget for the contract (ABC) in the amount of Nine Hundred Ninety-Two Thousand Pesos (P 992,000.00).**

Scope of Work:

- Electrical Design and Analysis.
- Mobilization of manpower, equipment, and supplies.
- Supply and installation of Electrical Sub-meter at Platinum Building. This includes the pipe laying and rewiring works.
- Supply and installation of Circuit Breakers and Sub-meter at Titanium Building. This includes the pipe laying and rewiring works.
- Supply and installation of Gypsum Board Single Wall Drywall at the Electrical Room of Titanium Building.
- Provisions of Electrical As-Build Plans.
- Commissioning and Testing.
- All equipment, labor, materials, and supplies needed for the implementation of works and restoration works (*if applicable*) are considered included in the contract cost.
- Please submit the accomplished Bill of Quantity together with your Quotation/Proposal

Qualified bidders should submit their quotations to the address below **on or before May 25, 2023 (Thursday), 10:00 AM**. Failure to strictly comply with the deadline and general conditions shall automatically disqualify the bidder/s from the bidding process. Winning bidder will be required to submit additional requirements as stipulated in the IRR of RA 9184.

PCHRD reserves the right to reject any or all quotations, to waive formality therein and to accept offers that may be considered most advantageous to the government.

For further information, please refer to:

Mr. Cirio D. Pangan Jr.

Secretariat, Bids and Awards Committee

Philippine Council for Health Research and Development

PCHRD Saliksik Building, Sikap Street,

DOST Main Compound, Gen. Santos Ave., Bicutan, Taguig City

Email: procurement@pchr.dost.gov.ph

Tel. Nos. 8837-2931 or 8837-2924 loc. 504 or 506

Fax No. 8837-7536 or 8837-2924

(sgd.)

MARIA VIOLETA G. INTIA

Chair, BAC

PROJECT :
 OWNER :
 LOCATION :
 SUBJECT :
 SCOPE :

REHABILITATION/IMPROVEMENT OF THE OFFICE SPACE AT TITANIUM BUILDING
 PHILIPPINE COUNCIL FOR HEALTH RESEARCH AND DEVELOPMENT
 DOST COM. GEN. SANTOS AVE. BICJTAN TAGUIG CITY
 BILL OF QUANTITIES
 ELECTRICAL WORKS

DESCRIPTION OF WORK	QTY	UNIT	MATERIAL COST	LABOR COST	OCM	12% VAT	UNIT COST	TOTAL COST
I. GENERAL REQUIREMENTS								
1. Electrical Design and Analysis	1	lot						
2. Mobilization/Demobilization & Hauling	1	lot						
3. As-Built Plan	1	lot						
4. Temporary Facilities	1	lot						
Subtotal								
II. Platinum Building								
1. THHN Wire 80mm2	36	m						
2. THHN Wire 22 mm2	30	m						
3. THHN Wire 14 mm2	220	m						
4. THHN Wire 8 mm2	82	m						
5. THHN Wire 5.5 mm2	1	roll						
6. THHN Wire 3.5 mm2	1	roll						
7. Watt-Hour Meter 200 amp with Meter Base and complete fitting & Accessories	4	sets						
8. Solder less connector #250 MCM	3	pcs						
9. Solder less connector # 50mm2	16	pcs						
10. Solder less connector #30mm2	6	pcs						
11. PVC Pipe 50mm dia.	3	pcs						
12. PVC Pipe 40mm dia.	5	pcs						
13. PVC Pipe 32mm dia.	3	pcs						
14. PVC Adaptor w/ locknut 50mm dia.	12	pairs						
15. PVC Adaptor w/ locknut 40mm dia.	16	pairs						
16. PVC Adaptor w/ locknut 32mm dia.	10	pairs						
17. PVC Elbow 40mm dia.	4	pcs						
18. PVC Cement 500 cc	2	can						
19. Electrical tape	15	rolls						
20. Rubber tape	8	rolls						
21. Wire Gutter 0.30m x 1.5m x 0.20m	2	sets						
Subtotal								
III. Titanium Building								
1. THHN Wire 50 mm2	108	m						
2. THHN Wire 14 mm2	65	m						
3. THHN Wire 8 mm2	30	m						
4. THHN Wire 5.5 mm2	1	roll						
5. THHN Wire 3.3 mm2	3	rolls						
6. Circuit Breaker 63 Amp at 3 Pole (Miniature Type)	3	sets						
7. Main Circuit 6 Branches at 3P MCB Branches 4-16 @ 2 Phase, 6-20 @ 2 Phase	3	sets						
8. Watt-Hour Meter 200 amp 3 Phase with Meter Base and complete fitting & Accessories	1	sets						
9. Watt-Hour Meter 60 Amp 3 Phase with Meter Base, Complete fitting and accessories	3	sets						
10. Solder less connector # 250 MCM	3	pcs						
11. Solder less connector #30mm2	4	pcs						
12. PVC Pipe 50mm dia.	4	pcs						
13. PVC Pipe 40mm dia.	5	pcs						
14. PVC Pipe 32mm dia.	5	pcs						
15. PVC Adaptor w/ locknut 50mm dia.	16	pcs						
16. PVC Adaptor w/ locknut 40mm dia.	15	pcs						
17. PVC Adaptor w/ locknut 32mm dia.	20	pcs						
18. Electrical Tape	5	rolls						
19. Rubber Tape	3	roll						
20. Wire Gutter 0.30m x 1.00m x 0.20m	2	sets						
21. Wire Gutter 0.30m x 0.8m x 0.20m	1	sets						
22. Gypsum Board Single Wall drywall with framing	10	sq. m.						
Subtotal								
GRAND TOTAL								

Note: All equipment, labor, materials and supplies needed for the implementation of works and restoration works (if applicable) are considered included in the contract cost.

Prepared by:
